

**Section 00040 - SC-296 (REIDVILLE RD) LEFT TURN LANES**

<b>Section</b>	<b>Item</b>	<b>Quantity</b>	<b>Units</b>	<b>Unit Cost</b>	<b>Total Cost</b>
1031000	MOBILIZATION	1	LS		
1050800	CONSTRUCTION STAKES, LINES & GRADES	1	LS		
1071000	TRAFFIC CONTROL	1	LS		
2012000	CLEARING AND GRUBBING WITHIN CONSTRUCTION LIMITS	1	LS		
2025000	REMOVAL & DISPOSAL OF EXISTING ASPHALT PAVEMENT	1,340	SY		
2026000	REMOVAL & DISPOSAL OF EXISTING CONCRETE PAVEMENT	67	SY		
2031000	UNCLASSIFIED EXCAVATION	3,250	CY		
2032000	ROCK EXACVATION	250	CY		
2103000	FLOWABLE FILL	6	CY		
3100320	HOT MIX ASPHALT AGGREGATE BASE COURSE - TYPE B	950	TON		
3069900	MAINTENANCE STONE	100	TON		
4011004	LIQUID ASPHALT BINDER PG64-22	161	TON		
4013990	MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	1,660	SY		
4020330	HOT MIX ASPHALT INTERMEDIATE COURSE TYPE C	580	TON		
4020330	HOT MIX ASPHALT INTERMEDIATE COURSE TYPE C (LEVELING)	340	TON		
4030330	HOT MIX ASPHALT SURFACE COURSE TYPE CM	810	TON		
6051120	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	232	SF		
609115A	PAVEMENT MARKINGS(TEMPORARY-PAINT)-4" WHITE SOLID LINES	7,700	LF		
609135A	PAVEMENT MARKINGS(TEMPORARY-PAINT)-24" WHITE SOLID LINES	100	LF		
609115B	PAVEMENT MARKINGS(TEMPORARY-PAINT)-4" YELLOW SOLID LINES	10,400	LF		
609160A	PAVEMENT MARKINGS(TEMPORARY-PAINT)-WHITE SINGLE ARROW	4	EA		
609180A	PAVEMENT MARKINGS(TEMPORARY-PAINT)-WHITE WORD 'ONLY	2	EA		
6271010	4" WHITE SOLID LINES (PVT. EDGE LINES) THERMO. - 90 MIL.	3,900	LF		

6271025	24" WHITE SOLID LINES (STOP/DIAG LINES)-THERMO.-125 MIL	50	LF		
6271030	WHITE SINGLE ARROWS (LT, STRGHT, RT) THERMO.-125 MIL.	4	EA		
6271035	WHITE WORD MESSAGE "ONLY" -THERMOPLASTIC - 125 MIL.	2	EA		
6271074	4" YELLOW SOLID LINES(PVT.EDGE LINES) THERMO - 90 MIL.	5,190	LF		
6300005	PERMANENT CLEAR PAVEMENT MARKERS- MONO-DIR.- 4"X4"	8	EA		
6301100	PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	65	EA		
6510105	FLAT SHEET, TYPE III, FIXED SZ. & MSG. SIGN	71	SF		
6531210	U-SECTION POST FOR SIGN SUPPORTS - 3P	99	LF		
7141112	15" RC PIPE CUL.-CLASS III	92	LF		
7141113	18" RC PIPE CUL.-CLASS III	228	LF		
7141114	24" RC PIPE CUL.-CLASS III	304	LF		
7141123	18" RC PIPE CUL.-CLASS IV	168	LF		
7142512	15" R. C. PIPE CUL. BEVELED END SECTN-CL 3	2	EA		
7142513	18" R. C. PIPE CUL. BEVELED END SECTN-CL 3	4	EA		
7142514	24" R. C. PIPE CUL. BEVELED END SECTN-CL 3	1	EA		
7143013	18" R. C. PIPE CUL. BEVELED END SECTN-CL 4	2	EA		
7149999	CLEANING EXISTING PIPE	131	LF		
	CATCH BASIN -TYPE 16 W/ MANHOLE	4	EA		
7191250	CATCH BASIN -TYPE 9 W/ MANHOLE	1	EA		
7192107	MANHOLE WITH STANDARD 4' X 4' BOX	2	EA		
7192215	24" X 36" JUNCTION BOX	2	EA		
7203110	CONCRETE CURB & GUTTER (1'-6")	300	LF		
7205000	CONCRETE DRIVEWAY (6" UNIFORM)	62	SY		
8041020	RIP-RAP (CLASS B)	137	TON		
8048210	GEOTEXTILE FOR EROSION CONTROL UNDER RIPRAP(CLASS 2)TYPE C	170	SY		
8051100	STEEL BEAM GUARDRAIL	225	LF		
8052210	END TERMINAL - TYPE B	1	EA		
8052300	END TERMINAL - TYPE T	1	EA		
8100100	PERMANENT COVER	1.652	AC		
8100200	TEMPORARY COVER	0.826	AC		

8101110	STRAW OR HAY MULCH WITH TACKIFIER	1.239	AC		
8104005	FERTILIZER (NITROGEN)	166	LB		
8104010	FERTILIZER (PHOSPHORIC ACID)	166	LB		
8104015	FERTILIZER (POTASH)	166	LB		
8105005	AGRICULTURAL GRANULAR LIME	3304	LB		
8151203	HYDRAULIC EROSION CONTROL PRODUCT (HECP) - TYPE 3	1.239	AC		
8151209	HYDRAULIC EROSION CONTROL PRODUCT (HECP) - TYPE 1 AS TRACER	0.760	AC		
8151101	TURF REINFORCEMENT MATTING (TRM) TYPE 1	0.750	MSY		
8151102	TURF REINFORCEMENT MATTING (TRM) TYPE 2	0.130	MSY		
8151111	TEMPORARY EROSION CONTROL BLANKET (CLASS A)	1.300	MSY		
8151112	TEMPORARY EROSION CONTROL BLANKET (CLASS B)	1.500	MSY		
8152007	SEDIMENT TUBE	600	LF		
8153000	SILT FENCE	660	LF		
8156219	INLET STRUCTURE FILTER - TYPE A	12	LF		
				<b>TOTAL:</b>	